WHITMAN COUNTY PUBLIC WORKS
SMALL WORKS WORKSHEET

PROJECT NAME: 2018 Road Stabilization Project in the Pullman, WA Area

DESCRIPTION: (Materials, Application, Supplies, Equipment)
Whitman County is soliciting quotes for delivery and application of Magnesium Chloride to sections of 4 roads for a total of 8.06 miles of treated roadway. Roads to have material applied are as follows:

- Country Club Rd. 1.69 miles @ 26' wide
- Brayton Rd. 3.23 miles @ 20' wide
- Hilty Rd. 2.63 miles @ 19' wide
- Sunset Rd .51 miles @ 22' wide

Whitman County will do all prep work and traffic control for the project. Successful bidder will deliver and apply two .25 gallons/square yard applications for a total of .50 gallons/square yard applied. Bidder must use a metered distributor for an accurate and even application. Bidder will coordinate with Whitman County to insure roadway is prepared properly prior to application. Whitman County would like to target a May 22nd, 2018 start date for this project. Whitman County crews work 10-hour days Monday thru Thursday. Application should be for an estimated total of 99,574 square yards and 49,787 gallons applied knowing that the actual gallons and/or tons may differ. Material delivered must be large enough in quantity to complete at least one road per day.

This is considered a public works project so prevailing wage applies. A copy of the wages paid statement will need to be provided to Whitman County at the end of the project. Invoices will be paid within 30 days of receipt.

All delivered materials, equipment, application and supply costs, plus tax, should be included in the quote. Please provide costs per ton and an estimated total cost **not** including tax.

Cost per ton **$**_____

Total estimated costs (not including tax) **$**_____

Delivery and application May 22nd thru May 24th

QUOTES MUST BE RETURNED BY: **March 30, 2018**

Contact: Brandon Kruger – Ext. 5203

Whitman County Public Works: (509) 397-4622 FAX (509) 397-6210